Kaukajärven Jääkeskus Oy · Kaukajärvi Ice Centre, Tampere

CONDITIONS FOR IN-ICE LOGOS, SEASON 2026–2027

Issued in Tampere on 29 June 2026 · Effective 1 July 2026 until the melt-out of May 2027

Ref.: KJK-JM-2026-04
Order form: JM-12
Version: 3
Replaces: v2 of 19 June 2025

1. NOTICE SUMMARY

Kaukajärven Jääkeskus Oy operates the two indoor ice sheets of the Kaukajärvi Ice Centre, Jääkellarinkatu 4, 33710 Tampere. This notice sets the only conditions under which sponsor logos and artwork may be placed in the ice, and replaces version 2 in full. The old ammonia plant was replaced in spring 2026 by a carbon dioxide (CO2) plant, so both sheets are now built thinner and the logo layer sits at a new depth (Section 3). Contracts signed under version 2 keep their agreed price, but the technical rules below apply to them from 1 July 2026.

Ice sheets	Halli 1 (main rink, 60 × 30 m, 1,650 seats); Halli 2 (training rink, 60 × 26 m)
How to order	Form JM-12 to the Commercial Office, Room 2.07, Mon–Fri 08:30–15:30
Not covered	Dasher-board panels and glass stickers (Board Advertising Terms KJK-MY-2026-02)

2. ICE BUILD CALENDAR

Logos are painted only while a sheet is being built, in the painting window below. Artwork must reach the Commercial Office by 15:00 on the artwork deadline. Halli 1 loses its ice twice in the season for dry-floor events, and each rebuild is a chance to add or change painted logos.

TABLE 1. ICE BUILDS AND ARTWORK DEADLINES, SEASON 2026–2027

Rink	Ice build	Artwork deadline	Plant start	Painting window	First skating
Halli 2	Summer build	Fri 3 Jul 2026	Mon 20 Jul 2026	Fri 24 Jul	Wed 29 Jul
Halli 1	Season build	Fri 17 Jul 2026	Mon 3 Aug 2026	Fri 7 – Sat 8 Aug	Thu 13 Aug
Halli 1	Rebuild after concert (13–14 Nov)	Fri 30 Oct 2026	Mon 16 Nov 2026	Thu 19 Nov	Sat 21 Nov
Halli 2	Christmas repaint	Fri 4 Dec 2026	Mon 21 Dec 2026	Tue 22 Dec	Sun 27 Dec
Halli 1	Rebuild after trade fair (25–28 Feb)	Fri 19 Feb 2027	Mon 1 Mar 2027	Thu 4 Mar	Sat 6 Mar
Both	Melt-out	—	Off: Mon 10 May 2027	—	—

3. TECHNICAL CONDITIONS

All painting is done by the Centre's own ice crew. Advertisers may watch from the home bench but may not walk on the ice or bring their own paint.

Fictional document created for testing a question-answering system. All names, figures and organisations are invented.

- **Paint:** only JääKuva W-series water-based ice paint, supplied by Pirkan Pintatuote Oy; at most 5 colours from the W-series palette card (edition 2026) plus the white base. No metallic, glitter or fluorescent pigments.
- **Layer depth:** logos are painted onto the white base when the ice is 6 mm thick. Halli 1 is then flooded to a total of 28 mm, so at least 22 mm of clear ice covers each logo; Halli 2 is flooded to 32 mm. Under version 2 the logo layer was at 10 mm and Halli 1 was built to 38 mm.
- **Ice temperature:** the surface is held at −3.5 °C ±0.5 °C while painting, until the second sealing flood has frozen.
- **Clear zones:** no artwork within 30 cm of a red or blue line, inside a goal crease, or within 50 cm of a face-off spot.
- **Film and mesh:** film logos are supplied by the advertiser on perforated polyester film no thicker than 0.25 mm and are laid only in the boards-band and bench-apron positions. Mesh is accepted only in the Halli 2 end zone. Both must reach Gate C rolled, not folded, 3 working days before laying.

4. LOGO POSITIONS AND SEASON FEES

Fees are per logo and season for the sheet named, invoiced half on signature and half on 1 December 2026, and exclude VAT at 25.5 %. Halli 1 logos lost at the November or March rebuild are repainted free if the artwork is unchanged.

TABLE 2. IN-ICE LOGO POSITIONS AND SEASON FEES 2026–2027 (EUR, EXCL. VAT)

Position	Max. size (m)	Method	Logos per sheet	Halli 1 fee	Halli 2 fee
Centre-ice circle	4.0 diameter	Paint	1	11,400	4,200
Neutral zone	3.5 × 2.0	Paint	2	6,900	2,600
Attacking zone, outside circles	2.5 × 1.5	Paint	4	4,700	1,800
End zone, behind goal line	3.0 × 1.2	Paint (mesh in Halli 2)	2	3,850	1,450
Boards band, along side boards	6.0 × 0.8	Film	4	5,250	1,950
Bench apron	4.0 × 1.0	Film	2	2,300	900

Until 30 June 2026 the Halli 1 centre-ice circle cost EUR 10,600; that price applies only to contracts signed before that date. Each registered tenant club may place one Halli 2 logo for its own youth section free of charge (not in the centre-ice circle).

5. FROM ORDER TO PAINTED ICE

1. The advertiser sends form JM-12 and vector artwork (PDF or SVG) by the artwork deadline in Table 1.
2. The ice crew returns a colour proof within 4 working days; the advertiser approves it in writing within 3 working days.
3. The Commercial Manager countersigns the proof and confirms the content meets the Centre's advertising rules.
4. After painting and flooding, the Ice Master measures the ice thickness at 9 fixed points and alone decides whether the sheet may reopen for skating.

Fictional document created for testing a question-answering system. All names, figures and organisations are invented.

Late artwork. Artwork up to 5 working days late is accepted only if the Ice Master confirms crew time, with a late-handling surcharge of EUR 380 (excl. VAT) per logo. Artwork more than 5 working days late is held over to the next build of that sheet in Table 1.

6. CHANGES DURING THE SEASON

Changes are ordered on form JM-12 with box C ticked. Work that closes a sheet is done on Sunday or Monday nights after 22:30.

TABLE 3. MID-SEASON CHANGES AND CHARGES (EUR PER LOGO, EXCL. VAT)

Change	Min. lead time	Charge	Sheet closed
Exchange of a film logo (same position)	10 working days	640	3 h
Blank-out of a painted logo (painted over in white)	5 working days	520	6 h
New painted logo outside a rebuild (shave and repaint)	15 working days	1,480	2 nights
Touch-up of a faded or scratched logo	2 working days	0	2 h
Reinstatement after a plant failure	—	0	As needed

7. RESPONSIBILITIES, DAMAGE AND CANCELLATION

Advertiser or club	Artwork, rights to trademarks, proof approval, supply of film and mesh
Commercial Manager (Satu Mäkiranta)	Contracts, invoices, countersigning proofs, advertising content
Ice Master (Jarkko Lehtisalo)	Painting schedule, ice crew, thickness checks, reopening a sheet
Refrigeration duty engineer	Plant start and stop, slab set points, plant failures (24 h tel. +358 3 512 4400)

If a sheet is lost through a plant failure or power cut, all logos are reinstated at the Centre's cost; for a logo out of the ice for more than 10 days, the advertiser is credited one thirty-sixth of its season fee for each further full week. An order may be cancelled free of charge until the artwork deadline of its build; after that 25 % of the season fee is due, and after painting the full fee.

BEFORE SENDING FORM JM-12

□ Rink, position and ice build chosen from Tables 1 and 2

□ Vector artwork with W-series colour codes, fonts converted to outlines

□ Named contact for proof approval, with mobile number

Satu Mäkiranta, Commercial Manager

Jarkko Lehtisalo, Ice Master

Fictional document created for testing a question-answering system. All names, figures and organisations are invented.